

To all Bidders.

ERRATA 1

Bid490-INSTALLATION OF SOLAR WATER HEATING SYSTEM AND REQUIRED ASSOCIATED INFRASTRUCTURE

Below are some final consolidated points for consideration in your tender response:

- Regarding the **sizing of the system**:
 - Maintain the initial sizing of **13 m² of collectors and 1 300 L of hot water storage for each building**, as stated in the ToR as the minimum spec.
 - This spec already takes into account the high hot water consumption that is expected with each building.
 - This could possibly avoid the back and forth redesigning of system with AEE-Intec during the SOLTRAIN application process which was raised as a potential concern by bidders.
- Mr Banie van Dyk has agreed to send what **plans of building, roof and technical drawings** he can find by close of business today.
 - We are hoping to forward these accordingly as soon as they are received, however it may cause unnecessary waiting times if we delay sending this communique.
- Please also take into account that the **military plumbers experience problems** with existing geysers where they need to frequently be replaced.
 - It seems that water interruptions can cause build-up of sand/silt in the municipal water system (filtered through sand filters on the AFB Hoedspruit).
- SANDF members to be shadowing the installer are **certified artisans**.
- **Inspection and verification** of the installed system will be financed with SOLTRAIN funding.
- A **contingency for unforeseen additional cost incurred**, within reason and subject to SANEDI approval, will be made available through SANEDI.

- **Forex fluctuations** effecting SOLTRAIN funding will be for consideration between the bidder and SOLTRAIN (AEE ITEC)
- SANEDI would be able to make an **initial upfront payment** after contract signature from 15% to 50%, as negotiated during contract placement with the successful bidder.
- **10%** of the tender award will be **retained** pending final sign off of the project.
- The military has specifically requested **no work or mounting** to be done on the **existing asbestos roofing**.

Regards

SANEDI Procurement